

Thornapple/Robley Septic to Sanitary Sewer Conversion

PROJECT UPDATE - Oct 23, 2018

Road replacement work on Thornapple Drive is scheduled to begin between 7:00 and 7:30 a.m. on Friday, October 26th. Road replacement work on Robley Lane is scheduled to begin between 7:00 and 7:30 a.m. on Monday, October 29th. This work will consist of excavating the existing roadway down approximately 9" and then installing 7-1/2" of asphalt. The time to complete the work up to this stage is estimated at approximately one week, weather permitting.

During this process, there will be several days where commuters will be driving on a compacted stone base until the new asphalt is installed. All driveways and roadways will be ramped with stone to maintain access. Please note that when the final 1-1/2" course of asphalt is installed, it will replace the 9" of roadway that was removed.

Please allow time in your schedule for delays that you may encounter during this roadwork. The contractor will make every effort to maintain access to your property and the adjacent roadways during the excavation work, but there may be short periods where access to your property will be limited.

Thank you for your continued patience during this phase of the project.

If you have any questions, please contact :
Village Engineer Tom Cappello at 216-731-6255 or
Service Director Doug Metzung at 440-442-5506 or
send an email to contactus@mayfieldvillage.com.